

EOLA Power LLC 8782 NW 18th Terrace

Miami, FL 33172 Phone: (800)399-7414

Quote Information				
Quote #	11019	Quoted on Date	8/15/2022	
Quote Description	V3-Riello UPS Replacement-Liebert AP356			

Customer	information		
Site	Company	Alachua County	
	Billing Address	Street	
		City	
		State	
		Zip code	
	Site /	Street	1100 SE 27th St.
	Shipping Address	City	Gainesville
		State	FL
		Zip code	32641
	Name	Gerald D Bailey	
Contact	Phone	352-548-1259	
	Email	gbailey@alachuad	county.us

Contact Information						
e number 800-399-7414						
ess 8782 NW 18th Terrace Miami, FL 33172						

EOLA | A Critical Power Company

8782 NW 18th Terrace Miami, FL 33172 / Telephone : + 1 (800)399-7414



EOLA Power LLC 8782 NW 18th Terrace

Miami, FL 33172 Phone: (800)399-7414

Quote	ed Iten	ns			
Item	Qty	Description	Part #	Unit Price	Extended Price
1	1.00	Riello 60kva UPS Solution w/ Ex MBP and 42P Distribution. Riello Sentryum UPS rated at 60kVA/60kW configured for 208V input and 208/120V output at 60 Hz without batteries includes 4 switches. CODE:DS3UK60SD300RUA Dimensions: 23.6"x 38.6"x 61.4"	Riello 60kva UPS Solution w/BP42P	\$77,321.6 5	\$77,321.65
		90843 Wall Mount Maintenance Bypass with 42P Distribution Voltage: 208/120VAC, 3PH/4W/G Breaker Size: 250A AIC Rating: 75k Interlock: Kirk-Key Locks standard - configuration #02 Dimensions: 25.5"W x 11.0"D x 64.1"H			
		Weight: 200 Lbs Color: Black (MB) Battery Cabinet 50kVA on Casters with a 350A Breaker, 1 String of (20) HRL12540WFR Batteries for a runtime of 18 min, Dim-29"Wx31.5"Dx59"H			
		Weight 2400 lbs. UTP Ethernet connection SNMP V3 (slot in card). UL Listed. CODE: YSKCSA4BUL			
		Includes Startup			
2	1.00	INCLUDES 3 YEAR FULL WARRANTY Provide alternate power source and (2) 200 amp panels to provide temporary power to all critical circuits being fed from UPS #1 in the CCC building. This portion of the project will take place several days in advance of the UPS swap out to the new unit, provided by and installed by EOLA power. When the new unit is set in place, connected, and running, we will swap all of the circuits back in to the new unit, connect and label accordingly. We will then remove all of the temporary power source. During this period there will be NO UPS backup for all circuits, but will be emergency fed from the generator if needed. We need a week in advance to install the temporary power source from panel E1 in the main electrical room approximately 1 00' west of the Data room. Total of (2) outages with a maximum of a fifteen minutes each shall be expected, but more than likely, will be only a few minutes for each occasion. Rigging-Setting UPS in place along with battery cabinet and Bypass Cabinet. Rigging and disposal Includes:		\$21,087.5 0	\$21,087.50

	A 3.5% processing fee will be assessed for all payments paid via credit card				
Grand Total:					\$118,534.15
Sales Tax (7.000%)					\$0.00
Subtotal:					\$118,534.15
10					
9					
8					
7					
6					
5					
34	1.00	Delivery and staging of new UPS. FREIGHT Additional Services: Resources for Rental 80-100kva 208/208 UPS(Up to 1 Month From Rental Delivery Date), Inside Delivery, Conduit/Material required to minimize outages, and any additional resources to ensure UPS System Replacement Project	FREIGHT Additional Services	\$3,000.00 \$17,125.0 0	\$3,000.00 \$17,125.00
		Removal and disposal of old UPS and Batteries per EPA regulations.			

EOLA | A Critical Power Company

8782 NW 18th Terrace Miami, FL 33172 / Telephone : + 1 (800)399-7414