



# ***Alachua County Budget and Fiscal Services Procurement***

Larry M. Sapp, CPPB  
Procurement Manager

Darryl R. Kight, CPPB  
Procurement Supervisor

August 15, 2019

RE: Addendum #2

BID 19-912 NW 91st Street Sidewalk Project 918-7903

Dear Sir/Madam

Please be aware of the following clarifications regarding the above referenced Bid:

## **CLARIFICATIONS**

**ADD: BID 19-912 NW 91st St-ATT Executed UWS**  
**BID 19-912 UWS 190814 GRU WWW UWS Executed**  
**BID 19-912 UWS 190814 NW 91st St Cox UWS Executed**  
**See attached Utility Work Schedules**

**NOTE:** You should acknowledge receipt of this addendum on your Bid Form.

**End of Addendum # 2**

Sincerely,

*Theodore White*

Theodore White  
Procurement Agent

TW/bf

Alachua County  
UTILITY WORK SCHEDULE

UTILITIES  
04/18/2019

Page 1 of 4

Project: NW 91 <sup>ST</sup> ST SIDEWALK	Project Number: 7903
County: ALACHUA	Road: NW 91 <sup>ST</sup>
Description: NW 91 <sup>ST</sup> ST SIDEWALK (NORTH ROAD TO WALGREENS)	
Utility Agency/Owner (UAO): AT&T Florida	

A. Summary of Utility Work And Execution

	Estimated Time (calendar days)
Prior To Alachua County Project Construction	<u>0</u>
During Alachua County Project Construction	<u>19</u>
Total	<u>19</u>

This document has been developed as the method for a Utility Agency/Owner (UAO) to transmit to Alachua County (The County), the County's Contractor, and other right-of-way users, the location, relocation, adjustment, installation, and/or protection of their facilities, on this County project. The following data is based on the County's preliminary construction plans dated October 2016. Any deviation by the County or its contractor from the plans, as provided, may render this work schedule null and void. Upon notification by the County of such change, this utility may require additional days for assessment and negotiation of a new work schedule. This UAO is not responsible for events beyond the control of the UAO that could not reasonably be anticipated by the UAO and which could not be avoided by the UAO with the exercise of due diligence at the time of the occurrence. The UAO agrees to notify the County in writing prior to starting, stopping, resuming, or completing work. This schedule does not exempt the UAO from obtaining applicable permits required by the City.

UAO Project Representative: KEN ROUW

Telephone Number: 904.206.4320

UAO Field Representative: KIRBY SPENCER

Telephone Number: 386.366.4588

This document is a printout of a County form maintained in an electronic format and all revisions thereto by the UAO in the form of additions, deletions or substitutions are reflected only in an Appendix entitled "Changes to Form Document" and no change is made in the text of the document itself. Hand notations on affected portions of this document may refer to changes reflected in the above-named Appendix but are for reference purposes only and do not change the terms of the document. By signing this document, the UAO hereby represents that no change has been made to the text of this document except through the terms of the appendix entitled "Changes to Form Document".

You MUST signify by selecting or checking which of the following applies:

- ☒ No changes to forms document.  
☐ Appendix "Changes to Forms Document" is attached. Number of Attachment Pages.

Authorized Utility Agent:

  
(Signature)

Jonathan Ellzey  
(Printed Name)

Area Manager OSP Ping & Eng  
Design  
(Title)

6-24-19  
(Date)

\*\*Engineer of Record (EOR):

(Signature)

(Printed Name)

(Title)

(Date)

County 92  
Acceptance by District CFX:

  
(Signature)

JAMES FLEGERT  
(Printed Name)

CONTRACTS & DESIGN MANAGER  
(Title)

8/13/19  
(Date)

Alachua County  
**UTILITY WORK SCHEDULE**

UTILITIES  
04/18/2019

Page 2 of 4

<b>Project: NW 91<sup>ST</sup> ST SIDEWALK</b>	<b>Project Number: 7903</b>
<b>County: ALACHUA</b>	<b>Road: NW 91<sup>ST</sup> ST</b>
<b>Description: NW 91<sup>ST</sup> ST SIDEWALK (NORTH ROAD TO WALGREENS)</b>	
<b>Utility Agency/Owner (UAO): AT&amp;T Florida</b>	
<b>B.</b>	<b>Special Conditions / Constraints</b>
<p>1) The contractor is to contact <u>KIRBY SPENCER</u>, MGR OSP PIng &amp; Eng Design @ 386.366.4588, 5 business days prior to start of construction.</p> <p>2) AT&amp;T Florida "Estimated Calendar Days" is based on a five (5) day work week, Monday thru Friday, 8 hours a day. Any request for work activities outside that time frame will need to be coordinated at least one week in advance of required work.</p> <p>3) All staking of existing Right of Way to allow proper installation/relocation of AT&amp;T Florida facilities, as indicated on this Utility Work Schedule, shall be performed by the County and/or the County's contractor. The County's contractor shall coordinate with AT&amp;T Florida and stake the items requested. AT&amp;T Florida will give at least 36-hour advance notice for items needing staking.</p> <p>4) Any design changes during construction of this project that places AT&amp;T Florida facilities in conflict will void the time frame as given in Section "C" of the approved Utility Work Schedule.</p> <p>5) Hold/Guard/Protect &amp; Adjustment activities to be provided by AT&amp;T Florida master contractor who will work closely with the County's Contractor to eliminate conflicts. AT&amp;T Florida must have 24 hours' notice to mobilize.</p> <p>6) This Utility Work Schedule is contingent on weather / storms which affect AT&amp;T Florida's construction. AT&amp;T Florida resources can also be affected by weather not directly contacting the Florida region as AT&amp;T Florida supports other AT&amp;T districts in Florida &amp; other states.</p> <p>7) The County's Contractor &amp; Sub-Contractors shall at all times allow AT&amp;T Florida personnel access to all facilities within the project limits of this project as maybe required doe normal and emergency operation and maintenance of existing and proposed facilities.</p> <p>8) All cable damages must be reported to the repair department at 877.737.2478.</p>	

Alachua County  
**UTILITY WORK SCHEDULE**

UTILITIES  
04/18/2019

Page 3 of 4

Project: NW 91 <sup>ST</sup> ST SIDEWALK				Project Number: 7903				
County: ALACHUA				Road: NW 91 <sup>ST</sup> ST				
Description: NW 91 <sup>ST</sup> ST SIDEWALK (NORTH ROAD TO WALGREENS)								
Utility Agency/Owner (UAO): AT&T Florida								
C.	Disposition of Facilities (List All Existing & Proposed) on Project:							
ACT No.	UTILITY FACILITIES BY STATUS/ TYPE/SIZE/MATERIAL	From Station/ Offset	To Station/ Offset	Utility Work Activity Description	Dependent Activity	TCP Phase	Consecutive Calendar Days Prior      During	
	EXISTING FACILITIES							
1	Existing buried 50pr	0+00 28' Lt	1+72 3' Rt	Remain in place & in service	N/A	N/A	0	0
2	Existing buried 50 pr	1+72 3' Rt	3+02 3' Rt	Remain in place & in service	N/A	N/A	0	0
3	Existing buried 50pr	3+02 3' Rt	3+44 8' Rt	Remain in place & in service	N/A	N/A	0	0
4	Existing buried 25pr, 50pr & 100pr	3+44 8' Rt	3+44 37' Lt	Remain in place & in service	N/A	N/A	0	0
5	Existing buried 50pr	3+72 8' Rt	3+72 37' Lt	Remain in place & in service	N/A	N/A	0	0
6	Existing buried 300pr	3+44 8' Rt	5+34 8' Rt	Remain in place & in service	N/A	N/A	0	0
7	Existing buried 300pr	5+34 2' Rt	6+06 3' Rt	Remain in place & in service	N/A	N/A	0	0
8	Existing buried 50pr	6+06 3' Rt	6+06 25' Lt	Remain in place & in service	N/A	N/A	0	0
9	Existing buried 300pr	6+06 1' Rt	10+33 2' Lt	Remain in place & in service	N/A	N/A	0	0
10	Existing buried 300pr	10+33 2' Lt	10+77 2' Lt	HOLD/GUARD/PROTECT Remain in place & in service	N/A	N/A	0	5
11	Existing aerial 300pr	6+48 3' Rt o/s varies	16+70 2' Rt o/s varies	Remain in place & in service	N/A	N/A	0	0
12	Existing buried 200pr	8+29 2' Rt	8+29 33' Lt	Remain in place & in service	N/A	N/A	0	0
13	Existing buried 300pr	10+77 2' Lt	12+15 2' Lt	Remain in place & in service	N/A	N/A	0	0
14	Existing buried 300pr	12+15 8' Lt	12+98 8' Lt	Remain in place & in service	N/A	N/A	0	0
15	Existing buried 100pr	12+98 8' Lt	12+98 45' Lt	Remain in place & in service	N/A	N/A	0	0
16	Existing buried 50pr	14+08 2' Rt	14+08 30' Lt	Remain in place & in service	N/A	N/A	0	0

Alachua County  
UTILITY WORK SCHEDULE

UTILITIES  
04/18/2019

Page 4 of 4

	Project: NW 91 <sup>ST</sup> ST SIDEWALK				Project Number: 7903			
	County: ALACHUA				Road: NW 91 <sup>ST</sup> ST			
	Description: NW 91 <sup>ST</sup> ST SIDEWALK (NORTH ROAD TO WALGREENS)							
	Utility Agency/Owner (UAO): AT&T Florida							
C.	Disposition of Facilities (List All Existing & Proposed) on Project:							
ACT No.	UTILITY FACILITIES BY STATUS/ TYPE/SIZE/MATERIAL	From Station/ Offset	To Station/ Offset	Utility Work Activity Description	Dependent Activity	TCP Phase	Consecutive Calendar Days Prior      During	
	EXISTING FACILITIES							
17	Existing buried 300pr	12+98 2' Lt	16+70 2' Lt	Remain in place & in service	N/A	N/A	0	0
18	Existing Cross-Connect Cabinet	16+70 3' Lt		Remain in place & in service	N/A	N/A	0	0
19	Existing buried 300pr	16+70 2' Rt	20+73 2' Rt	Remain in place & in service	N/A	N/A	0	0
20	Existing buried 50pr	18+02 2' Rt	18+02 40' Lt	Remain in place & in service	N/A	N/A	0	0
21	Existing Buried 300pr	16+70 2' Lt	18+44 11' Rt	Placed out of service & remain	N/A	N/A	0	0
22	Existing buried 50pr	16+70 2' Lt	18+44 10' Rt	Placed out of service & remain	N/A	N/A	0	0
23	Existing buried 300pr	18+44 11' Rt	20+31 8' Rt	Remain in place & in service	N/A	N/A	0	0
24	Existing buried 50pr	18+44 10' Rt	20+31 6' Rt	Remain in place & in service	N/A	N/A	0	0
25	Existing pedestal/splice closure	20+31 5' Rt		Remain in place & in service	N/A	N/A	0	0
26	Existing buried 900pr	20+31 6' Rt	20+55 54' Rt	Remain in place & in service	N/A	N/A	0	0
27	Existing buried 400pr	20+31 7' Rt	20+55 56' Rt	Remain in place & in service	N/A	N/A	0	0
	PROPOSED FACILITIES							
28	Proposed directional bore w/4" PVC Flex-pipe	16+70 2' Lt	18+44 5' Rt	Directional Bore	N/A	N/A	0	7
29	Proposed copper cable-size TBD	16+70 2' Lt	18+44 5' Rt	Pull-in cable	N/A	N/A	0	4
30	Splicing & Cutover Copper			Cable placed	N/A	N/A	0	
31	Copper Testing			Cable spliced	N/A	N/A	0	3
	END OF SCHEDULE							



# UTILITY WORK SCHEDULE

Page 1 of 3

<b>Project:</b> NW 91st Street Sidewalk	<b>County Project No:</b> 7903
<b>County:</b> Alachua	<b>Road:</b> NW 91st Street
<b>Description:</b> New sidewalk from NW 39th Ave to North Road	
<b>Utility Agency/Owner (UAO):</b> GRU Water/Wastewater	

<b>A.</b>	<b>Summary of Utility Work And Execution</b>
-----------	--

Estimated Time  
(calendar days)

Total Time Prior To County Project Construction 11  
 Total Time During County Project Construction 0

This document has been developed as the method for a Utility Agency/Owner (UAO) to transmit to Alachua County (The County), the County's Contractor, and other right-of-way users, the location, relocation, adjustment, installation, and/or protection of their facilities, on this County project. The following data is based on County preliminary construction plans dated May 2018. The UAO agrees to be responsible for any delays and delay costs for any conflicts with UAO's facilities not identified by this work schedule. Any deviation by the County or its contractor from the plans, as provided, may render this work schedule null and void. Upon notification by County of such change, this utility may require additional days for assessment and negotiation of a new work schedule. This UAO is not responsible for events beyond the control of the UAO that could not reasonably be anticipated by the UAO and which could not be avoided by the UAO with the exercise of due diligence at the time of the occurrence. The UAO agrees to notify the County in writing prior to starting, stopping, resuming, or completing work. This work schedule does not exempt the UAO from obtaining any permits required by the County.

UAO Project Representative: Andrew Roberts  
 UAO Field Representative: Keith Halbrook

Telephone Number: 352-393-1639  
 Telephone Number: 352-681-7459



  

This document is a printout of a form maintained in an electronic format and all revisions thereto by the UAO in the form of additions, deletions or substitutions are reflected only in an Appendix entitled "Changes to Form Document" and no change is made in the text of the document itself. Hand notations on affected portions of this document may refer to changes reflected in the above-named Appendix but are for reference purposes only and do not change the terms of the document. By signing this document, the UAO hereby represents that no change has been made to the text of this document except through the terms of the appendix entitled "Changes to Form Document".

You MUST signify by selecting or checking which of the following applies:

☐ No changes to forms document.  
☐ Appendix "Changes to Forms Document" is attached \_\_\_\_\_ Number of Attachment Pages.

<b>Authorized Utility Agent:</b>  _____ (Signature) Andrew Roberts, P.E. _____ (Printed Name) Supervising Engineer _____ (Title) 08/12/19 _____ (Date)	<b>**Engineer of Record (EOR):</b> _____ (Signature) _____ (Printed Name) _____ (Title) _____ (Date)	<b>Acceptance by County:</b>  _____ (Signature) JAMES FLEGERT, PE _____ (Printed Name) CONTRACTS & DESIGN MANAGER _____ (Title) 8/13/19 _____ (Date)
---	--	---

(\*\*When requested by the County, the EOR will attest to compatibility of plans, specifications and Utility Work Schedule)

## UTILITY WORK SCHEDULE

<b>Project:</b> NW 91 <sup>st</sup> Street Sidewalk	<b>County Project No.:</b> 7903
<b>County:</b> Alachua	<b>Road:</b> NW 91 <sup>st</sup> Street
<b>Description:</b> New sidewalk from NW 39 <sup>th</sup> Ave to North Road	
<b>Utility Agency/Owner (UAO):</b> GRU Water/Wastewater	
<b>B.</b>	<b>Special Conditions / Constraints</b>
<p>1. In the event damage occurs to GRU utilities:</p> <ul style="list-style-type: none"> <li>a. Call GRU W/WW Emergency Dispatch – 352-334-2711</li> <li>b. Notify Andrew Roberts at 352-393-1639 or another GRU Representative at 352-393-1610</li> <li>c. Issue Cut/Damage Report to the County</li> </ul> <p>2. The Roadway Contractor shall notify Keith Halbrook with GRU at 352-681-7459 for advance notification and scheduling of during construction utility adjustments, as listed on this UWS. GRU requests a 14 day advance notification for all pipe relocations and 5 days for meter or valve adjustments by GRU during construction.</p> <p>3. The Roadway Contractor (and any Subcontractors) shall at all times allow GRU personnel to access all facilities within the limits of this project as may be required for normal and emergency operations and maintenance of GRU's facilities.</p> <p>4. The Roadway Contractor shall prevent the entry of asphalt, concrete, debris, and soil material into the water valve box for access operations. If any materials (asphalt, soil, or otherwise) enter the water valve box assembly such that proper engagement of the standard valve wrench on the operating nut is impeded the the Roadway Contractor shall remove such material to the satisfaction of GRU, at no additional cost.</p> <p>5. GRU W/WW reserves the ability to review the bid price for the installation of any designated work or adjustments by the Roadway Contractor and to self-perform the work based on the costs of the proposed work.</p> <p>6. All construction materials and methods for potable water, wastewater, and reclaimed water systems shall be in conformance with GRU's most recent Potable Water, Wastewater, &amp; Reclaimed Water System Design Standards, Construction Details, Construction Standards, and Approved Materials Manual. The Roadway Contractor shall submit shop drawings, cut sheets, and other similar materials to the GRU W/WW Field Representative for review and approval prior to ordering materials.</p> <p>7. For materials for water valve and meter adjustments, please call Emory Prevatt, GRU Water Distribution O&amp;M Manager, at 352-642-4063 Monday through Thursday from 7am to 4pm. Materials will be provided to the Roadway Contractor within 72 hours of notification.</p> <p>8. DEFINITIONS:</p> <ul style="list-style-type: none"> <li>• <b>LOCATING</b> - The use of test holes by vacuum excavation or compatible non-destructive equipment of a critical point along a subsurface utility facility's path by exposing the underground utility facility and allowing the precise measurements of the depth and horizontal position to be collected.</li> <li>• <b>DESIGNATING</b> - Utilizing electromagnetic, magnetic, sonic, and other energy fields for determining the existence and approximate horizontal location of underground utilities. Underground utility facilities will be marked by stakes, flags, paint, or other suitable materials in varying combinations dependent upon surface conditions using American Public Works Association Utility Location Coordination Council Color Codes.</li> <li>• <b>PROTECT</b> - Protection shall include, but not limited to, permittee's use of an on-site representative during active construction activities. During excavation operations, representatives may be required to physically expose underground utility facilities, provide any necessary support to the facilities, and/or cover aerial facilities as deemed necessary to aid construction.</li> </ul>	

## UTILITY WORK SCHEDULE

Project: NW 91 <sup>st</sup> Street Sidewalk		County Project No: 7903		
County: Alachua		Road: NW 91 <sup>st</sup> Street		
Description: New sidewalk from NW 39 <sup>th</sup> Ave to North Road				
Utility Agency/Owner (UAO): GRU Water/Wastewater				
C.	Disposition of Facilities (List All Existing & Proposed) on Project:			
UTILITY FACILITIES BY STATUS/ TYPE/SIZE/MATERIAL/OFFSET TO BASELINE FROM STA TO STA	DESCRIPTION OF UTILITY WORK	DEPENDENT ACTIVITIES	M.O.T PHASE NUMBER	CONSECUTIVE CALENDAR DAYS
GRU Water Valves: - STA: 14+50; 02' RT (Concrete)	Roadway Contractor to perform all of GRU's water valve adjustment work via a Utility Work by Highway Contractor Agreement between the County and GRU. GRU to provide materials for water main valve box adjustments. Materials will be provided to the Roadway Contractor within 72 hours of notification.	N/A	N/A	N/A
GRU Water Mains: - STA: 15+08; 08' RT	Locate and Protect ex. 8" PVC water main. GRU to confirm water main depth and adjust as needed.	Pre-construction	N/A	5
- STA: 15+24; 03' RT	GRU to remove ex. fire hydrant and install new fire hydrant.	Pre-construction	N/A	1
- STA: 17+49; 11' RT	Locate and Protect ex. 2" PVC water main. GRU to confirm water main depth and adjust as needed.	Pre-construction	N/A	5
GRU Wastewater Gravity Manholes:	N/A	N/A	N/A	N/A
GRU Wastewater Gravity Mains:	N/A	N/A	N/A	N/A
GRU Wastewater Force Main Valves:	N/A	N/A	N/A	N/A
GRU Wastewater Force Mains: - STA: 01+50; 18' RT to 09+25; 18' RT	Locate and Protect ex. 6" PVC Wastewater Force Main	N/A	N/A	N/A
END OF UTILITY WORK SCHEDULE				



# UTILITY WORK SCHEDULE

Page 1 of 3

Project: ACPW NW 91st Street Sidewalk Project		County Project No: 7903	
County: Alachua		Road: NW 91 <sup>st</sup>	
Description: Sidewalk project			
Utility Agency/Owner (UAO): Cox Communications			
<b>A.</b>	<b>Summary of Utility Work And Execution</b>		
<div style="text-align: right; margin-bottom: 10px;">Estimated Time (calendar days)</div> <div style="display: flex; justify-content: space-between;"> <div>Total Time Prior To County Project Construction</div> <div>_____</div> </div> <div style="display: flex; justify-content: space-between;"> <div>Total Time During County Project Construction</div> <div>_____</div> </div> <p style="font-size: small; margin-top: 20px;">This document has been developed as the method for a Utility Agency/Owner (UAO) to transmit to Alachua County (The County), the County's Contractor, and other right-of-way users, the location, relocation, adjustment, installation, and/or protection of their facilities, on this County project. The following data is based on County preliminary construction plans dated _____. The UAO agrees to be responsible for any delays and delay costs for any conflicts with UAO's facilities not identified by this work schedule. Any deviation by the County or its contractor from the plans, as provided, may render this work schedule null and void. Upon notification by County of such change, this utility may require additional days for assessment and negotiation of a new work schedule. This UAO is not responsible for events beyond the control of the UAO that could not reasonably be anticipated by the UAO and which could not be avoided by the UAO with the exercise of due diligence at the time of the occurrence. The UAO agrees to notify the County in writing prior to starting, stopping, resuming, or completing work. This work schedule does not exempt the UAO from obtaining any permits required by the County.</p> <div style="display: flex; justify-content: space-between; margin-top: 20px;"> <div>UAO Project Representative: <u>Randy H. Ehlers</u></div> <div>Telephone Number: <u>352-337-2009</u></div> </div> <div style="display: flex; justify-content: space-between;"> <div>UAO Field Representative: <u>Randy H. Ehlers</u></div> <div>Telephone Number: <u>352337-2009</u></div> </div> <p style="font-size: small; margin-top: 20px;">This document is a printout of a form maintained in an electronic format and all revisions thereto by the UAO in the form of additions, deletions or substitutions are reflected only in an Appendix entitled "Changes to Form Document" and no change is made in the text of the document itself. Hand notations on affected portions of this document may refer to changes reflected in the above-named Appendix but are for reference purposes only and do not change the terms of the document. By signing this document, the UAO hereby represents that no change has been made to the text of this document except through the terms of the appendix entitled "Changes to Form Document".</p> <p style="font-size: small; margin-top: 10px;">You MUST signify by selecting or checking which of the following applies:</p> <div style="margin-top: 10px;"> <input type="checkbox"/> No changes to forms document.  <input type="checkbox"/> Appendix "Changes to Forms Document" is attached _____ Number of Attachment Pages.         </div> <div style="display: flex; justify-content: space-between; margin-top: 20px;"> <div style="width: 30%;"> <p>Authorized Utility Agent:</p> <div style="text-align: center; margin-top: 10px;">               _____              (Signature)              Randy H. Ehlers              _____              (Printed Name)              Construction Planner              _____              (Title)              9/27/2018              _____              (Date)         </div> </div> <div style="width: 30%;"> <p><b>**Engineer of Record (EOR):</b></p> <div style="text-align: center; margin-top: 10px;">             _____              (Signature)              _____              (Printed Name)              _____              (Title)              _____              (Date)         </div> </div> <div style="width: 30%;"> <p>Acceptance by County:</p> <div style="text-align: center; margin-top: 10px;">               _____              (Signature)              JAMES FLEGERT              _____              (Printed Name)              CONTRACTS &amp; DESIGN MANAGERS              _____              (Title)              8/13/19              _____              (Date)         </div> </div> </div> <p style="font-size: small; margin-top: 10px;">(**When requested by the County, the EOR will attest to compatibility of plans, specifications and Utility Work Schedule)</p>			

## UTILITY WORK SCHEDULE

Project: ACPW NW 91 <sup>st</sup> St Sidewalk project		County Project No.: 7903	
County: Alachua		Road: NW 91 <sup>st</sup> Street	
Description: Sidewalk			
Utility Agency/Owner (UAO): Cox Communications			
B.		Special Conditions / Constraints	
<p>No foreseeable conflicts.</p>			

## UTILITY WORK SCHEDULE

Project:		County Project No:		
County: Alachua		Road:		
Description:				
Utility Agency/Owner (UAO):				
C.	Disposition of Facilities (List All Existing & Proposed) on Project:			
UTILITY FACILITIES BY STATUS/ TYPE/SIZE/MATERIAL/OFFSET TO BASELINE FROM STA TO STA	DESCRIPTION OF UTILITY WORK	DEPENDENT ACTIVITIES	M.O.T PHASE NUMBER	CONSECUTIVE CALENDAR DAYS