Alachua Co. State Attorney's Office - 2nd Floor

min of 1 hr RATED DOORS. A.U.

GENERAL NOTES

1. SEE SPECIFICATIONS FOR ROOM FINISH AND DOOR SCHEDULES SECTION 09200 AND 08000 RESPECTIVELY.
2. PATCH ALL WALLS, FLOORS AND CEILINGS TO MAINTAIN FIRE RATING. FINISH TO MATCH
3. REMOVE EXISTING FILM, CLEAN AND REPLACE FILM ON EXTERIOR GLAZING, ENTIRE BUILDING (ALTERNATE #1 REMO AND REPLACE FILM; ENTIRE BLDG.)
4. SEE ELEVATIONS SHEET FOR BASE BID SCOPE
5. FIELD VERIFY DIMENSIONS
6. EXISTING WALLS TO BE EXTENDED ABOVE NEW CEILING HEIGHTS AS REQ'D

CONSTRUCTION NOTES

1. INFILL EXISTING OPENING; PATCH TO MATCH & FINISH FLUSH WITH EXISTING WALL
2. VERIFY DIMENSION; NEW WALL TO BE PATCHED TO MATCH & FINISHED FLUSH WITH EXISTING CONDITION
3. PROVIDE NEW 5/8" GYP BD FINISH, NEW METAL FURRING @16" O.C. AS NEEDED TO PROVIDE SMOOTH AND FLUSH FINISH
4. REMOVE & REPLACE EXTERIOR WALL WITH REUSED GRANITE AND NEW ALUMINUM FRAME AND GLAZING; REMOVE CARPET, PLACE CONC. AS NECESSARY TO ELIMINATE SLOPE IN EXIST. SLAB CHIP/ROUGHEN EXISTING SLAB TO ASSURE PROPER BONDING
5. REMOVE & REPLACE EXTERIOR WALL WITH NEW ALUMINUM FRAME & GLAZING, REMOVE CARPET, PLACE CONC. AS NECESSARY TO ELIMINATE SLOPE IN EXIST. SLAB CHIP/ROUGHEN EXISTING SLAB TO ASSURE PROPER BONDING
6. REMOVE & REPLACE CRACKED GLASS (SEE ELEV'S FOR LOC.)
7. REMOVE & REPLACE EXISTING STOREFRONT SYSTEM WITH NEW STOREFRONT SEE SHEET A6 FOR FRAME TYPE. REMOVE THRESH.
8. FIELD VERIFY LOCATION OF STAIRWELL PARTITIONS; ALIGN STL. STUDS W/ BEAMS AS REQ'D. (SEE DETAILS)
9. SOUND ATTENUATION BATTS IN WALL; PROVIDE BATTS ABOVE CEILING, ENTIRE ROOM (REMOVE ONE SIDE OF WALL & INSTALL SOUND BATTS @ EXIST. WALLS.
10. PROVIDE SOLAR FILM ON EXISTING GLAZING, THOROUGHLY CLEAN GLAZING PRIOR TO APPLYING NEW SOLAR FILM (INCLUDE IN BASE BID)

LEGEND

- EXISTING WALL TO REMAIN
- NEW STEEL STUD WALL
- DEMO EXISTING WALL
- NEW 1 HOUR FIRE WALL SEE DETAIL 16-A7
- RATE EXISTING WALL (PROVIDE 1 HR RATING)
- A.P. ACOUSTIC PARTITION (N.I.C.)
- △ REFERENCE TO INTERIOR ELEVATIONS SEE SHEETS A8 & A9
- ① REFERENCE TO CONSTRUCTION NOTES
- Ⓔ FRAME TYPE SEE SHEET A6
- FEC FIRE EXTINGUISHER CABINET, VERIFY EXACT LOCATION WITH BUILDING CODES

753.33 SY - _CPT 24x24 | 1906 SF - _LVT 6x48 Luxe Plank | 2012.97 LF - _VB